



QTY	PART	MATERIAL	ITEM	DESCRIPTION
1	1	ASCR3	FIBERGLASS	37 6'-0" ICI (OPTIONAL) BELOW BOTTOM PHASE ONLY
3	3	ASCR2	FIBERGLASS	36 6'-0" ICI (OPTIONAL)
1	1	ENR01280	GALV	5 OPER. PIPE 2" SCH 80 x 21'-0"
4	4	-	GALV	34 1/2" X 4" LAG BELLS
2	2	-	GALV	31 5/8" X 5" LAG BELLS
1	1	ASCR7	GALV	27 OPERATOR HING. BRKT. ASSY
1	1	ASCR5	GALV	31 OPERATOR HANDLE ASSY
3	3	000187230NS	GALV	30 CONTACT MOUNTING PRECAST
6	6	-	-	29 INSULATOR 115KV 12096
-	-	-	-	28 -
-	-	-	-	27 -
-	-	-	-	26 -
-	-	-	-	25 -
3	3	ASCR20	COPPER	24 PIVOT CAP ASSY
3	3	000113020M	BRASS	23 ARCTING SPRING LATCH
3	3	000113020M	BRASS	22 ARCTING SPRING CLAMP
3	3	ASR12	GALV	21 ARCTING HORN ASSY
2	2	ASCR20	COPPER	20 JAW ASSY, 115 KV 600 A RH
2	2	ASR10	COPPER	19 BLADE ASSY, 115 KV 600 A RH
1	1	ASCR9	COPPER	18 JAW ASSY, 115 KV 600 A LH
1	1	ASR11	COPPER	17 BLADE ASSY, 115 KV 600 A LH
2	2	ASCR8	COPPER	16 JAW ASSY, 115 KV 1200 A RH
2	2	ASR6	COPPER	15 BLADE ASSY, 115 KV 1200 A RH
1	1	ASCR7	COPPER	14 JAW ASSY, 115 KV 1200 A LH
1	1	ASR6	COPPER	13 BLADE ASSY, 115 KV 1200 A LH
3	3	ENR01300	GALV	12 OPER. PIPE 2" SCH 80 x 21'-0"
2	2	ASCR5	GALV	11 PIPE CAPPING 2" IPS WITH PERKING SET SCREWS
3	3	ASCR7	GALV	10 PIPE GUIDE ASSY
2	2	ASCR1	ALUM	9 PHASE GUIDE W/IES
1	1	0002000G	GALV	8 PIPE SPACER 6" 5"
1	1	ASCR8	-	7 THRUST BEARING ASSY, W/144,163
3	3	ASCR5	GALV	6 7" PIPE LEMER ASSY
3	3	ENR01300	ALUM	5 REAR ROD 1" SCH 80 x 80"
6	6	ASCR3	GALV	4 1" CLEVIS ASSY, 3 WITH SET SCREWS
3	3	ASCR4	ALUM	3 PIVOT ASSY, (2-250, 1-115)
3	3	000200000M	GALV	2 INSULATOR PRECAST
3	3	ASCR2	ALUM	1 ICI-115 FRAME ASSY

NOTE F

REV	DATE	BY	MARK	DESCRIPTION
REVIZING	DATE	BY	MARK	DESCRIPTION
1	02-28-94	JAC		ISSUE FOR CONSTRUCTION
2	02-28-94	JAC		ISSUE FOR CONSTRUCTION

115 KV

800/1200

1001-115-6/12 (2-RH, 1-LHM)

WOOD POLE MOUNTING

DRAWING # SK7375 SHEET 1 OF 1

TURNER ELECTRIC CORPORATION
FAIRVIEW HEIGHTS, IL., USA

